

T1-R3

Master plan, round 3 — off the grid where i

Round 2, with the grid broken in the three places where a 45° line creates space out of nothing.

- Entrance: the vestibule's glass wall turns 45°, so the front door opens onto a diagonal view of the hall, the stair and the garden beyond; guests are steered to the living and the WC, and the coat wall gains a full 2 m run.
- Upstairs junction: the prayer room's corner is cut at 45°. Its door now faces you as you turn from the stair, the corridor corner widens into a small landing, and the icon wall keeps a clean east wall.
- Secret den: the kids bath ceiling drops to 2.3 m (it needs a service void anyway) and the 0.85 m above becomes a hidden loft den reached by a ladder in the playroom — a room that costs no floor area.
- The E1 drain stack is wrapped into a walnut AV column in the living room instead of a boxed-out corner.
- Everything that worked in round 2 stays: one suite door, dressing gallery, hers walk-in, windowed shower room, utility lobby, lockable lounge.

Changes vs round 2

- Vestibule: straight glass screen → 45° glazed wall with a 1.2 m double door; guest WC door slid to the street end of the vestibule.
- Kitchen ↔ hall glass slider re-centred (1.2 m) clear of the new vestibule.
- Prayer room: north-east corner cut at 45° with the door on the diagonal (4.2 → 4.0 m²); corridor junction +0.2 m².
- Loft den over the kids bath (≈ 2.9 × 1.5 m, 0.85 m high) + ladder; walnut column around the E1 stack downstairs.

Colour key

- Living
- Kitchen / dining
- Parents
- Children
- Baths
- Service / storage
- Prayer
- Flexible room
- Circulation